

Thermal Report

Location	Observation	Severity
Master Bedroom Ceiling	Cold anomaly (ΔT 5.2°C), moisture suspected.	Critical
Basement North Wall	Cold spot near crack. Thermal image unavailable.	High
Kitchen HVAC Vent	Temperature variation inconsistent with inspection report.	Medium

Thermal Findings: Relative humidity near ceiling estimated at 85%. Basement thermal image not available. Kitchen readings show conflicting telemetry requiring manual verification.